

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,578 *0000*

LEASE NAME VOSHELL "A"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

4950' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 13 TWP. 19S RGE. 29 XE or (W)

LEASE OPERATOR Slawson Exploration Company, Inc.

COUNTY LANE

ADDRESS 104 S. Broadway, Suite 200 Wichita, KS. 67202-4165

Date Well Completed 4-1-91

PHONE#(316 263-3201 OPERATORS LICENSE NO. 3988

Plugging Commenced 4-1-91 5:30 AM

Character of Well D&A

Plugging Completed 4-1-91 7:30 AM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 1, 1991 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	306	8 5/8"	306'	none <u>4-25-91</u> <u>APR 25 1991</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot 50 sx. @ 2170', 80 sx. @ 1250', 50 sx. @ 340', 20 sx. @ 40', 15 sx. in rathole

Total: 250 sx. 60/40 Pozmix, 6% gel, 1/4# flo-seal per sack

(If additional description is necessary, use BACK of this form.)
 (Allied Cementing Co., Inc)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Company, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.

L. D. Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

(Address) L. D. Davis
R.R. 1 Box 183 B
Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1991



My Commission Expires: 5-20-93

Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

EFFECTIVE DATE: 3-25-91

State of Kansas

NOTICE OF INTENTION TO DRILL

101-21,578-0000

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 15 1991
month day year

NW NW NW Sec 13 Twp 19 S, Rg 29 East West

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 South Broadway, Suite 200
City/State/Zip: Wichita, Kansas 67202-4165
Contact Person: Bob Jenkins
Phone: (316) 263-3201

4950'
4950' feet from South line of Section
feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC.

County: Lane
Lease Name: VOSHELL "A" Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2803' Gr. (Seis) feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 300'
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: None
Projected Total Depth: 4650'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond other

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth 0'

DWR Permit #: Buy from Dighton
Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: APR 02 1991

Exp. 9/20/91

STATE OF KANSAS COMMISSION AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Grey Pardson 578

SPUD DATE 3-23-91 INIT. CP

LENGTH SURFACE PLANNED SEC 13 1/2

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbs. when done bbbs.

RATHOLED AHEAD? Y SIZE HOLE
SURFACE PIPE 2 1/2" @ 306 CONDUCTOR
ANHYDRITE T- 2141 B- 2168 ELEVATION

TD 4650 FORMATION _____

RAN PIPE @ _____ SX	DV TOOL _____	ALT II DONE _____
_____	_____	_____
Arbuckle Plug @ _____	Ft. W/ _____	SX
Hug./Council @ _____	Ft. W/ _____	SX
Anhydrite Base @ <u>2170</u>	Ft. W/ <u>50</u>	SX
1/2 Base Anyh. @ <u>1250</u>	Ft. W/ <u>80</u>	SX
1/2, 1/2 Plug @ <u>625</u>	Ft. W/ <u>50</u>	SX
Bottom Surface @ <u>340</u>	Ft. W/ <u>50</u>	SX
40' Plug @ <u>40</u>	Ft. W/ <u>10</u>	SX
RAT HOLE CIRC/W <u>15</u> SX	MOUSE HOLE W/ _____	SX
WATER WELL _____ SX (Irr. Well _____)	Pond _____	
TECHNICIAN <u>SM</u>	DATE <u>3-29-91</u>	Hauling _____
TYPE OF CEMENT <u>60/40 67s</u>	<u>1/4" 10 Seal Plus</u>	
STARTING TIME <u>4:00</u>	(AM/PM) DATE <u>4-1-91</u>	
COMPLETION TIME <u>7:30</u>	(AM/PM) DATE <u>4-1-91</u>	
CEMENT COMPANY <u>1711ed</u>		