

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,526-0000

LEASE NAME Voshell

WELL NUMBER 3

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 13 TWP. 19 SRGE. 29 ~~XXXXXX~~ (W)

COUNTY Lane

Date Well Completed 10-15-89

Plugging Commenced 10-15-89

Plugging Completed 10-15-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-15-89 (date)

by State Plugger, Dodge City District (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4685'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	260.04'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud 15 minutes. 1st plug from 2170' to 1970' w/50 sx. 2nd plug from 1200' to 880' w/50 sx. & 1 sack of hulls. 3rd plug from 290' to 130' w/40 sx. 4th plug from 40' to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. 12-5-89


Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton  
150 N. Main, Suite 801  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 89

Sharan J. Branstetter Notary Public

My Commission Expires: May 18, 1993



Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 15 89  
month day year

C... SE ... Sec 13 Twp 19 S, Rg 29 W East West

OPERATOR: License # 5393  
Name: A. L. Abercrombie, Inc.  
Address: 150 N. Main #801  
City/State/Zip: Wichita, Ks. 67202  
Contact Person: Jack L. Partridge  
Phone: 316-262-1841

1320'  
1320'  
feet from South line of Section  
feet from East line of Section  
(Note: Locate well on Section-Plot Below)

CONTRACTOR: License #: 5422  
Name: Abercrombie Drilling, Inc.

County: Lane  
Lease Name: Voshell Well #: 3  
Field Name: (Hineman Mine) UNKNOWN  
Is this a Prorated Field? ... yes X no  
Target Formation(s): LKC-Marmation  
Nearest lease or unit boundary: 1320  
Ground Surface Elevation: Unknown feet MSL  
Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 60-180'  
Depth to bottom of usable water: 1100'  
Surface Pipe by Alternate: ... 1 X 2  
Length of Surface Pipe Planned to be set: 240'  
Length of Conductor pipe required: None  
Projected Total Depth: 4650  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage X Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OAWO: old well information as follows:  
Operator: N/A  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location:

... well ... farm pond ... other  
DWR Permit #: Unknown Apply for Permit  
Will Cores Be Taken?: ... yes X no  
If yes, proposed zone: N/A

Exp. 3/21/90


Set 240' of 8 5/8 on 10-6-89

200' Alt. II Req.

AFFIDAVIT

PUSHER Wipac Drilling  
TD 4685 FORMATION  
SURFACE PIPE 8 5/8 @ 260  
ANHYDRITE 2141-2120 ELEVATION  
STARTING TIME & DATE 10:45 AM - 10:25 PM  
COMPLETION TIME & DATE 6:45 PM  
1st PLUG @ 2170 FT. WI 50 SX  
2nd PLUG @ 1200 FT. WI 80 SX  
3rd PLUG @ 290 FT. WI 40 SX  
4th PLUG @ 40 FT. WI 10 SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI SX  
WATER WELL PLUGGED WI SX  
CEMENT COMPANY B.S. Titah  
TECHNICIAN A.L.  
TYPE OF CEMENT 60/40 6%

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1989  
CONSERVATION DIVISION  
Wichita, Kansas



6 months of effective date.)  
Spud date: Agent:

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is complete;
  - Obtain written approval before disposing or injecting salt water.