

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,785-0000

LEASE NAME Paris

WELL NUMBER 1

730 Ft. from S Section Line

1995 Ft. from E Section Line

SEC. 14 TWP. 19S RGE. 29W (X) or (W)

COUNTY Lane

Date Well Completed 11/27/00

Plugging Commenced 12:15AM 11/27/00

Plugging Completed 3:15AM 11/27/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DENIS ROBERTS OIL

ADDRESS 3904 Fairway Drive Hays, KS 67601

PHONE# (785) 625-8526 OPERATORS LICENSE NO. 32322

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Steve Middleton (date)

by 11/23/00 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	209	8 5/8	209.15	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each as  
1st Plug @ 2200'w/50sks 5th Plug @ 40'w/10sks Circulated 1st Plug 15 Minutes W/47 Vis Mud.  
2nd Plug @ 1370'w/80sks 10sks In Mouse Hole Plugs Displaced with mud  
3rd Plug @ 700'w/40sks 15sks In Rat Hole Total 245sks 60/40Poz 6%Gel W/1#EC/sk  
4th Plug @ 250'w/40sks By Allied Cementing Completed @ 3:15AM 11/27/00

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DENIS ROBERTS OIL

STATE OF Ks COUNTY OF Ellis, ss.

(Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.


(Signature) Denis Roberts

(Address) 3904 Fairway Hays, KS

SUBSCRIBED AND SWORN TO before me this 22 day of February, 192001

Chris Schneider  
Notary Public

My Commission Expires: 8-20-03



Form CP-  
Revised 05-0

OR

**ALLIED CEMENTING CO., INC.**

P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566

\*\*\*\*\*  
 \* INVOICE \*  
 \*\*\*\*\*

Invoice Number: 082836

Invoice Date: 11/26/00

Sold Denis Roberts Oil  
 To: 3904 Fairway Dr.  
 Hays, KS  
 67601

Cust I.D.....: RobeDe  
 P.O. Number...: Paris #1  
 P.O. Date.....: 11/26/00

Due Date.: 12/26/00  
 Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	147.00	SKS	6.3500	933.45	E
Pozmix	98.00	SKS	3.2500	318.50	E
Gel	13.00	SKS	9.5000	123.50	E
FloSeal	61.00	LBS	1.1500	70.15	E
Handling	245.00	SKS	1.0500	257.25	E
Mileage (39)	39.00	MILE	9.8000	382.20	E
245 sks @\$.04 per sk per mi					
Rotary Plug	1.00	JOB	580.0000	580.00	E
Mileage pmp trk	39.00	MILE	3.0000	117.00	E
Top Wood Plug	1.00	EACH	23.0000	23.00	E

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of \$ 280.51  
 ONLY if paid within 30 days from Invoice Date

Subtotal: 2805.05  
 Tax.....: 0.00  
 Payments: 0.00  
 Total....: 2805.05

RECEIVED  
 STATE OF KANSAS  
 COMMERCIAL TAX COMMISSION  
 2356.97