

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,598 0000

LEASE NAME Paris

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR Graceland Oil Company

SEC. 14 TWP. 19 SRGE. 29 (E) or (W)

ADDRESS P. O. Box 1068, Hays, KS 67601

COUNTY Lane

PHONE# (913)-625-0040 OPERATORS LICENSE NO. _____

Date Well Completed 9/21/91

Character of Well D&A

Plugging Commenced 9/21/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/21/91

The plugging proposal was approved on 9/21/91 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	304'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4670'-2200' 50 sks cement @ 310'

50 sks cement @ 2200' 10 sks cement @ 40'

80 sks cement @ 1400' 15 sks in rathole

50 sks cement @ 700' 10 sks in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graceland Oil Company

STATE OF KANSAS COUNTY OF RUSSELL, ss. 9-5-91

Kyle B. Branum

(Employee of Emphasis Oil Operations or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 91

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

GLENDA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS

Commission Expires: 2-6-92

BY APPT. EXPIRES 2-6-92

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. August .. 24 .. 1991 ..
 month day year ... SE SW SW ... Sec 14 ... Twp 19 ... S, Rg 29 ... East West

OPERATOR: License # 30033
 Name: GraceLand Oil Company
 Address: P.O. Box 1068
 City/State/Zip: Hays, KS 67601
 Contact Person: Ed Glassman
 Phone: (913)-625-0040

330 feet from South line of Section
 4290 feet from East line of Section
 (Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 8241
 Name: Emphasis Oil Operations

County: Lane
 Lease Name: Paris Well #: 1
 Field Name: Paris
 Is this a Prorated Field? ... yes no
 Target Formation(s): Lansing
 Nearest lease or unit boundary: 330
 Ground Surface Elevation: Est. 2840 feet MSL
 Domestic well within 330 feet: ... yes no
 Municipal well within one mile: ... yes no
 Depth to bottom of fresh water: 100
 Depth to bottom of usable water: 1200 (1400)
 Surface Pipe by Alternate: ... 1 2
 Length of Surface Pipe Planned to be set: 250
 Length of Conductor pipe required: N/A
 Projected Total Depth: 4650
 Formation at Total Depth: Mississippi
 Water Source for Drilling Operations:
 ... well farm pond ... other

Well Drilled For: Well Class: Type Equipment:
 ... Oil ... Inj X. Infield X. Mud Rotary
 ... Gas ... Storage ... Pool Ext. ... Air Rotary
 ... OAWO ... Disposal ... Wildcat ... Cable
 ... Seismic; ... # of Holes

If OAWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no
 If yes, total depth location: _____

DWR Permit #: _____
 Will Cores Be Taken?: ... yes no
 If yes, proposed zone: _____

AFFIDAVIT

200' Alt. II Req. SEP 25 1991 COMMISSION

Exp. 2/20/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S. 55-101, et. seq.
 It is agreed that the following minimum requirements will be met:

Pusher Tom Bill Owen
 SPUD DATE 9-12-91 INIT. CA
 LENGTH SURFACE PLANNED 280'
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 8 5/8" 30J CONDUCTOR
 ANHYDRITE T- 2167 B-2198 ELEVATION
 TD 4670 FORMATION MISSISSIPPI
 RAN PIPE @ DV TOOL ALT II DONE
 SX SX Y N
 Arbuckle Plug @ Ft. W/ SX
 Hug./Council @ Ft. W/ SX
 Anhydrite Base @ 2200 Ft. W/ 50 SX
 1/2 Base Anyh. @ 1400 Ft. W/ 80 SX
 1/2, 1/2 Plug @ 700 Ft. W/ 50 SX
 Bottom Surface @ 310 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
 WATER WELL SX (Irr. Well Pond _____)
 Hauling _____
 TECHNICIAN SM DATE 9-17-91
 TYPE OF CEMENT 60/40 5% 1/4 1/6 F/air plugging
 STARTING TIME 2:45 (AM/PM) DATE 9-21-91
 COMPLETION TIME 7:30 (AM/PM) DATE 9-2-91
 CEMENT COMPANY Allied

15-101-21598-0000

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Graceland Oil Company
P. O. Box 1068
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Paris WELL #1

LOCATION: SE SW SW
Section 14-19S-29W
Lane County, Kansas

LOGGERS TOTAL DEPTH: 4670'

ROTARY TOTAL DEPTH: 4670'

COMMENCED: 9/12/91

CASING: 8-5/8" @ 304' w/175 sks cement

ELEVATION: 2835' K.B.

COMPLETED: 9/21/91

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)


Dakota Sand	940'	Heebner	3973'
Shale	1048'	Lansing-Kansas City	4013'
Cedar Hills	1690'	Base Kansas City	4387'
Shale	1973'	Marmaton	4429'
Anhydrite	2164'	Mississippi	4639'
Shale	2198'	R.T.D.	4670'

RECEIVED
STATE OF KANSAS DEPT. OF REVENUE

SEP 25 1991

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on September 24, 1991.

My commission expires: February 6, 1992.

GLEND A R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92


Glenda R. Tiffin, Notary Public