

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME PARIS A

WELL NUMBER 2

660 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 14 TWP. 19 RGE. 29 (E) or (W)

COUNTY LANE

Date Well Completed SPUD 9/11/78

Plugging Commenced 05-22-97

Plugging Completed 05-22-97

LEASE OPERATOR JHS ENERGY, INC.

ADDRESS 1720 S. BELLAIRE ST. SUITE 1209, DENVER, CO. 80222

PHONE/(303) 757-8811 OPERATORS LICENSE NO. 31645

Character of Well SWD

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05-22-97 (date)

by DISTRICT 1 OFFICE KEVIN STRUBE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation _____ Depth to Top 4637 Bottom 4649 T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>SURFACE</u>	<u>0</u>	<u>259</u>	<u>8 5/8"</u>	<u>259</u>	<u>0</u>
	<u>PRODUCTION</u>	<u>0</u>	<u>4659</u>	<u>4 1/2"</u>	<u>4659'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Allied mixed 300# hulls, 250 sacks cement, 6% gel-pumped down casing, pressured up backside to 500#. Max pressure 600#, shut in 200#. Job started 1:10 pm and completed 2:00 pm

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JHS Energy, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph J. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph J. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 29 day of May, 1997

Bonnie L. Connell
Notary Public

My Commission Expires: April 8, 2001

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88

KANSAS DRILLERS LOG


API No. 15 — 101 — 20340-0000
County Number

S. 14 T. 19 R. 29W E W

Loc. S/2 S/2 SE

County Lane

640 Acres
N



Locate well correctly

Elev.: Gr. 2816

DF 2819 KB 2821

Operator

DONALD C. SLAWSON

Address

200 Douglas Building Wichita, Kansas 67202

Well No.

2 SWD

Lease Name

Paris 'A'

Footage Location

390'

feet from (N) 35 line

1320'

feet from (E) 20W line

Principal Contractor

Slawson Drilling Co., Inc.

Geologist

Don Moore

Spud Date

September 11, 1978

Total Depth

4660'

P.B.T.D.

4659'

Date Completed

September 21, 1978

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	28#	259'	60/40 poz	200	2% gel, 3% cc
Production	7 7/8"	4 1/2"	10.5#	4659'	Neat 50/50 poz	25 150	18% salt, 3/4% CFRT, 10# sugar

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3/4" bullet	4637-49
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8	4600	4600			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

500 gal mod 202

4637-49

INITIAL PRODUCTION

Date of first disposal

SWD 10/12/78

Producing method (flowing, pumping, gas lift, etc.)

vacuum

RATE OF PRODUCTION PER 24 HOURS

Oil

Gas

Water

Gas-oil ratio

bbls.

MCF

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

disposal 4637-49

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 2	Lease Name Paris 'A'	SWDW	
S 14 T 19 R 29 WE W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
0 - 1588 Sand and Shells			LOG TOPS
1588 - 3226 Shale			ANHY 2152 (+669)
3226 - 4160 Lime and Shale			B/ANHY 2178 (+641)
4160 - 4214 Lime			HEEB 3960 (-1139)
4214 - 4248 Lime and Shale			LANS 4004 (-1183)
4248 - 4660 Lime			STK SH 4284 (-1463)
4660 RTD			BKC 4362 (-1541)
			MA 4396 (-1575)
			PAW 4484 (-1663)
			L/CHER 4556 (-1735)
			MISS 4620 (-1799)
			LTD 4654 (-1833)
DST #1 4182-4214 (140 Zn) 30-30-30-30, WKB/5", Rec. 10' M, IFP 30-30#, ISIP 1221#, FFP 34-34#, FSIP 1213#, 120°. DST #2 4230-4248 (160 Zn) 30-30-30-30, WKB/15", Rec. 15' OSM, IFP 25-25#, ISIP 1118#, FFP 25-25#, FSIP 1049#, 118°. Drlg @ 4248' DST #3 4327-4340 (MD CRK) 30-60-45-75, WKBTO, Rec. 300' Wtr scum of oil on top stand. IFP 25-69#, ISIP 1264#, FFP 77-146#, FSIP 1256#, 125°. Circ. @ 4347' DST #4 4388-4414 (Marm Zn) 30-60-30-30, WKB/30", Rec. 5' Mud, IFP 8-17#, ISIP 51#, FFP 17-17#, FSIP 17# nrlo @ 4473'			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature R. J. THATCHER - Engineer Title September 28, 1978 Date		

DONALD C. SLAWSON

OIL PRODUCER

200 DOUGLAS BUILDING, WICHITA, KANSAS 67202
316/263-3201

November 16, 1978

Mr. Marvin W. Glotzbach, Geologist
Oil Field and Environmental Geology Section
Department of Health and Environment
740 Forbes Building
Topeka, Kansas 66620

Re: Donald C. Slawson
Paris 'A' Lease
Paris Field
S/2, Sec. 14-19S-29W
Lane County, Kansas
Disposal of Saltwater
Docket No. CD-10787 (C-19,464)

OPY

Dear Marvin:

On October 9, we cemented the subject well from
1,050 feet to the surface. Copies of the work
tickets on this job are enclosed for your informa-
tion.

Sincerely yours,

JIM THATCHER

Jim Thatcher

JT/jk

Enclosures

cc Mr. Frank Broadfoot

RECEIVED
KANSAS CORP COMM
1978 APR 11 A 10:51