

Harold Chambers

DAILY DRILLING REPORT

PROSPECT Voshell YEAR 1979 15-101-20386-0000
 LEASE Voshell WELL NO. 1 WELL LOCATION NE NW SW COUNTY Lane STATE KS
 DRILL SITE LEASE DESCRIPTION Sec. 13-19S-29W CODE _____
 OPERATOR Beren Corporation ELEVATION: GR 2812
 CONTRACTOR C-G Drilling Company DF _____
 GEOLOGIST Bob Lewellyn KB 2817
 DEVELOPMENT WELL PROSPECT TEST WELL X NOTIFY _____
 OWNERSHIP 1979 Program
 IDENTIFICATION Test Well

TOPS:

| | | | |
|------------|--------------|----------|--------------|
| Heebner | 3956 (-1139) | Cherokee | 4556 (-1739) |
| Toronto | 3971 (-1154) | Johnson | 4595 (-1778) |
| Lansing | 4002 (-1185) | Miss | 4622 (-1805) |
| BKC | 4362 (-1545) | T.D. | 4627 (-1810) |
| Marmaton | 4396 (-1579) | | |
| Altamont | 4444 (-1627) | | |
| Pawnee | 4486 (-1669) | | |
| Fort Scott | 4522 (-1705) | | |

MOVING IN & RIGGING UP June 18, 1979 SPUD June 18, 1979

SET 8-5/8" @ 315' w/ 225 sx 60-40 pozmix, 2% gel, 3% CC. P.D. 12:15 A.M. 6-19-79.
 Cement circulated.

| DATE | DEPTH | DST |
|---------|-------|---|
| 5/20/79 | 2115' | #1 4082 - 4110 ("E" "F") 30/45/120/90 |
| 5/21/79 | 2923' | 200' watery mud 1155/1139 25/47 57/139 |
| 6/22/79 | 3262' | |
| 6/23/79 | 3690' | #2 4172 - 4215 ("H") 30/45/60/60 |
| 6/24/79 | 3990' | 2600' water 1206/1206 37/774 774/1188 |
| 6/25/79 | 4110' | #3 4222 - 42 ("I") 30/30/30/30 |
| 6/26/79 | 4215' | 15' mud 1180/1044 22/36 37/39 |
| 6/27/79 | 4255' | |
| 6/28/79 | 4323' | #4 4246 - 55 ("J") 30/45/60/60 |
| 6/29/79 | 4344' | 1200' water 1236/1230 28/345 345/597 |

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 10 1979
 CONSERVATION DIVISION
 Wichita, Kansas

| | | | | | |
|----------------------------|-----------------------------|---------------|---------|-------|-------|
| 4324 - 44 ("L") #5 | 4280 - 4323 ("K") | | | | |
| 30/45/60/60 | 30/45/60/60 | (Strong blow) | | | |
| 1000' gas, 3270' clean oil | Fluid | % Oil | % Mud | % Gas | % Wtr |
| 1178/1193 69/886 902/1156 | 300 | 50 | 35 | 15 | 0 |
| | 300 | 25 | 40 | 25 | 10 |
| | 300 | 50 | 10 | 25 | 15 |
| | 300 | 40 | 5 | 30 | 25 |
| | 300 | 35 | 2 | 35 | 28 |
| | 800 | 5 | 0 | 0 | 95 |
| | 2300' total fluid recovered | | | | |
| | 1247/1240 | 75/589 | 606/958 | | |

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20386-0000

LEASE NAME Voshell #1

WELL NUMBER _____

SPOT LOCATION NE NW SW

SEC. 13 TWP. 19 SRGE. 29 W (E) or (W) (W)

COUNTY Lane

Date Well Completed _____

Plugging Commenced 7/22/85

Plugging Completed 7/22/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Finan. Ctr. Wichita, Ks. 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.O. 4627'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 315' | none |
| | | | | 5 1/2" | 4626' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only - No pipe recovery. Behind 5 1/2" was squeezed with 750 sacks cement.

Plugged well with 1 hull, 25 cement, 10 gel, 50 cement, 5 gel, & 125 sacks 60/40 poz 6% gel down 5 1/2". Plug fell, capped with ready-mix to surface.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26 day of July, 1985



My Commission expires: _____

Notary Public
JUL 29 1985