

API NUMBER 15-101-20454-0001

LEASE NAME Voshell "B" #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SE SW NW

SEC. 13 TWP. 19 SRGE. 29 W(E) of (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/22/85

Plugging Completed 7/22/85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Fianan. Ctr. Wichita, Ks. 67202

PHONE # (310) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	307'	none
				4 1/2"	4639'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plug job only - No pipe recovery. Behind 4 1/2" was squeezed with 550 sacks cement.

Ran 1 bull, 25 cement, 10 gel, 50 cement, 5 gel, & 125 sacks 60/40 poz 6% gel down 4 1/2". Plug fell, capped with ready-mix.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of July, 1985



My Commission expires: \_\_\_\_\_

Notary Public

JUL 29 1985  
7-29-85

DAILY DRILLING REPORT

15101-20454-0001

PROSPECT Voshell YEAR 1979  
 WELLSITE Voshell "B" WELL NO. 1 WELL LOCATION SE SW NW COUNTY Lane STATE KS  
 WELL SITE LEASE DESCRIPTION Sec. 13-19S-29W CODE \_\_\_\_\_  
 OPERATOR Beren Corporation ELEVATION: GR 2814  
 CONTRACTOR Blue Goose Drilling Company DF \_\_\_\_\_  
 GEOLOGIST Pat Balthazor KB 2821  
 DEVELOPMENT WELL  PROSPECT TEST WELL \_\_\_\_\_  
 OWNERSHIP 1979 Beren Program NOTIFY \_\_\_\_\_  
 IDENTIFICATION Development Well

ROCKS:	Anhydrite	2151 (+ 670)	Pawnee	4503 (-1682)
	Base Anhydrite	2176 (+ 643)	Fort Scott	4548 (-1727) -7
	Heebner	3962 (-1141)	Ck	4573 (-1752) -9
	LK	4003 (-1182) +2	Johnson Zone	4611 (-1790) -9
	Stark	4297 (-1476) -9	Miss	4635 (-1814) -2
	BKC	4379 (-1558) -9		
	Marmaton	4409 (-1588) -11		
	Alt	4461 (-1610) -10		

STARTING IN & RIGGING UP July 11, 1980 SPUD July 11, 1980  
8-5/8" @ 307' w/ 225 sx.

DATE	DEPTH	DST
4/80	2747'	#1 4162 - 4224 ("H") 30/30/30/30 2004' water 1169/1169 301/969 1069/1158
5/80	3385'	
6/80	3933'	#2 4227 - 4249 ("I") 30/30/30/30 60' mud, SSO 513/446 33/33 33/33
7/80	4224'	
8/80	4248'	#7 4438-4540 (L MM & Paw)#3
11/80	4440'	60/60/60/75 295' mud 1180/1169 100/145 167/190
12/80	4520'	4245 - 4261 ("J") 30 17' mud 46/
23/80	4600'	#4 4295 - 4315 ("K") 30/30/30/30 2340' water 1263/1281 229/742 835/1000
24/80	4640' RTD	Set 4 1/2" @ 4439'

3 TOPS:

Base Anhydrite	2148 (+ 673) +6
Heebner	2174 (+ 647)
LK	3960 (-1139)
Stark	4001 (-1180) +4
BKC	4295 (-1474) -4
Marmaton	4374 (-1553)
Heebner	4399 (-1578)
Pawnee	4457 (-1636)
Fort Scott	4499 (-1678) Johnson Zone 4610 (-1799)
Proke	4547 (-1726) -6 LTD 4641
	4570 (-1749)

RECEIVED #5  
 STATE CORPORATION COMMISSION

III 10 1985

CONSERVATION #6  
 Wichita, Kansas

#5 4324 - 4350 ("Mid Ck")
60/60/60/60
100' mud, 120' MC water
1172/1135 37/64 101/119
#6 4383 - 4440 (Pleas & Upr MM)
30/30/30/30
1464' oil
1036/1002 223/424 513/613