

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Trego County, Sec. 9 Twp. 13S Rge. 21 (E) (W) X

Location as "NE/CNW/SW" or footage from lines N/2 NE/4

Lease Owner Glen E. Armour DBA Western Oil Field Service

Lease Name Keller # 2 Well No.

Office Address P. O. Box 163 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 12-16-64 19

Application for plugging approved 12-17-64 19

Plugging commenced 12-24-64 19

Plugging completed 12-26-64 19

Reason for abandonment of well or producing formation Dry


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 3889 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				.8 5/8	208	None
				1 1/2	None	350

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar. Sanded to 3850'. Dumped 4 sacks of cement. Riggged up jacks. Shot pipe at 650'.

Working pipe. Shot pipe at 550' - 450' and 350'. Squeezed well with 30 sacks of mud and 50 sacks of cement.

Pulling pipe.

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 4 day of January 19 65

My commission expires May 27, 1965

Notary Public.

JAN 6 1965

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

OWNER:
LEASE:
LOCATION:

Hellar Drilling Company, Inc.
Keller #2
C W/2 NW NE, Sec. 9-13S-21W
Trego County, Kansas
February 2, 1961
February 13, 1961

COMMENCED:
COMPLETED:

Set 8-5/8" surface casing at 217' with 175 sacks cement. Set 4-1/2" string at 3991' with 165 sacks cement.

Depth	Description	Elevation	KB
0 - 205	Surface clay, sand, gravel		2227
205 - 218	Blue shale		
218 - 910	Shale & shells	Anhydrite	1615 /612
910 - 1175	Shale	Heebner	3492 -1265
1175 - 1320	Sand	Toronto	3511 -1284
1320 - 1510	Shale, shells	Lansing-Kansas City	3527 -1300
1510 - 1615	Shale, lime streaks	Base Kansas City	3769 -1542
1615 - 1660	Anhydrite	Marmaton	3843 -1616
1660 - 1675	Shale	Conglomerate	3909 -1682
1675 - 3540	Shale, lime	Arbuckle	3941 -1714
3540 - 3858	Lime		
3858 - 3956	Chert, lime		
3956 - 3992	Arbuckle		
3992	Rotary Total Depth		

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the KELLER #2, C W/2 NW NE, Section 9-13S-21W, Trego County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

BY D. L. Hellar
D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 16th day of February, 1961.

Wanda Lou Bruce
Notary Public

My commission expires March 6, 1961.