


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 29 Twp. 31 Rge. 8 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines CW/2 SW SE

Lease Owner Pickrell Drilling Co.

Lease Name Hestetler Well No. 1

Office Address 705 Fourth Natl. Bank Bldg. Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 11, 1967

Application for plugging filed Jan. 20, 1968

Application for plugging approved Jan. 23, 1968

Plugging commenced Jan. 23, 1968

Plugging completed Jan. 25, 1968

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Dec. 28, 1967

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Miss. Depth to top 4371 Bottom 4377 Total Depth of Well 4377 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203'	None
				5 1/2	4373'	3715'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 4377' to 4350'. Mixed and dumped 4 sx. of cement from 4350' to 4302'. Pulled casing. Mudded hole to 205'. Set 10' rock bridge from 205' to 195'. Mixed and dumped 25 sx. of cement from 195' to 120'. Mudded hole from 120' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.

Address P.O. Box 1082, Great Bend, Ka.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. W. Sebitts

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebitts
705 Fourth Natl Bank Bldg, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1968

L M Whiting

Notary Public.

My commission expires

May 10, 1970

Copy made WLB
5-12-67

15-077-20013-0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 4/3/67

Rotary Drilling Completed 4/12/67

LOCATION: No. 1 Hostetler "A"
W/2 SW SE Section 29-31S-8W
Harper County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" surface casing set at 203' and cemented with 165 sacks cement. Circulated. (137 jts.) 4 1/2" casing set at 4373' and cemented with 100 sacks cement. Complete at 3:30 AM, April 12, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

25	Sand
515	Red Rock
1335	Shale
1465	Shale & Lime Stringers
2470	Lime & Shale
2870	Shale
3070	Lime & Shale
3185	Shale
3455	Sandy Lime & Shale
3785	Shale
4376	Shale & Lime, RTD
4377	Log Total Depth

C. F. S.
4372'
4376'

Slope Tests
3000
3500
4000

S. L. M.
None

RECEIVED
STATE CORPORATION COMMISSION
1-23-68
JAN 23 1968
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 10th day of May, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting
Notary Public