

15-877-20046-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Bldg.
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15 - N/A

LEASE NAME Broce AB Unit

WELL NUMBER 2

1650 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 29 TWP. 31S RGE. 8 (E) or (W) (W)

COUNTY Harper

Date Well Completed 4-23-68

Plugging Commenced 3-22-95

Plugging Completed 3-28-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 110 N. Market, Suite 205 Wichita, KS 67202

PHONE#(316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-28-95 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4373 Bottom T.O. 4388

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	212	8 5/8	212	None
		0	4378	5 1/2	4378	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from feet to feet each set.
Squeezed 125 sx. thru hole between 776-783 (May, 1992). Set CIBP 4320. Perforate 1599-1600. Squeeze 1599-1600 w/ 35 sx. Perforate at 200 ft. Pump 20 sx. followed by wiper plug to 185 ft. Perforate at 170 ft. Could not circulate. Perforate at 100 ft. Mix and pump 40 sx., circulate to surface. SI with 300% standing pressure. (See copy of supervisors report attached).

Name of Plugging Contractor Pickrell Drilling Company, Inc. License No. 5123

Address 110 N. Market, Suite 205 Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) 110 N. Market, #205 Wichita, KS 67202



AND SWORN TO before me this 5th day of April, 19 95

Karen A. Mans McGee
Notary Public

My Commission Expires: 6-23-96

USE ONLY ONE SIDE OF EACH FORM