


15-077-00212-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 30 Twp. 31S Rge. 8 (E) 8 (W)  
Location as "NE/CNW/SW" or footage from lines SE/SW/SE  
Lease Owner Mull Drilling Company, Inc.  
Lease Name Asper Well No. #1  
Office Address 6405 E. Kellogg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Yes 19\_\_\_\_  
Application for plugging approved Yes 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 3-7 19 57  
Plugging completed \_\_\_\_\_ 3-10 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4365' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,604'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 4365'.  
Plugging started 3-7-57. Finished 3-10-57.  
Plugged off bottom with sand to 4335' and dumped 5 sacks cement.  
Shot 5 1/2" casing at 3604'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 25 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks cement for cap on well.

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1957.

My commission expires November 8, 1960.  
Betty S. Edman Notary Public.

PLUGGING  
FILE SEC 30 T. 31 R. 8W  
BOOK PAGE 143 LINE 33

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-57

ROTARY DRILLERS LOG

COMPANY : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMMENCED: 12-31-55  
 Wichita, Kansas

CONTRACTOR : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 1-12-56  
 Wichita, Kansas

CASTING RECORD: Set 8 5/8" @ 160' cemented with 125 sacks cement. LOCATION: ASPER #1  
 SE SW SE of Sec. 30-31E-8W  
 Harper County, Kansas

Set 5 1/2" @ 4365' cemented with 150 sacks cement.

( Figures indicate bottom of formation - measurements from top of Rotary Bushing. )

Clay	30	Lime & Shale	3947
Sand	50	Lime	4030
Red Rock	160	Lime & Shale	4094
Red Bed & Shells	450	Lime	4207
Shale & Shells	1290	Lime & Shale	4270
Lime & Shale	3030	Lime (Mississippian)	4365 R.T.D.
Shale, Sand & Lime	3301		

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

*Frank H. Purcell*  
 \_\_\_\_\_, SECRETARY  
 FRANK H. PURCELL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 24th day of January, 1956

*Ethel Zimmerman*  
 \_\_\_\_\_  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: January 28, 1957.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 2-26-57  
 FEB 26 1957

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 30 T. 31 R. 8 W  
 143 U. E. 33

*Handwritten notes:*  
 1-25-56  
 1-26-56