


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harper

County. Sec. 31 Twp. 31S Rge. 8W (E) (W)

Location as "NE/CNW&SW&" or footage from lines SW NW SW

Lease Owner Orville H. Parker

Lease Name Campbell Well No. 1

Office Address Box 791 - Ponca City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 5-4 19.55

Application for plugging filed 9-20 19.55

Application for plugging approved 9-22 19.55

Plugging commenced September 27 19.55

Plugging completed September 30 19.55

Reason for abandonment of well or producing formation not economically productive

If a producing well is abandoned, date of last production August 19.55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Mississippi Depth to top 4366 Bottom Total Depth of Well 4373 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION   | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-------------|---------|------|----|--------|--------|------------|
| Heebner     |         | 3369 |    | 8-5/8" | 252'   | None       |
| Douglas     |         | 3499 |    | 5-1/2" | 4367'  | 4006'      |
| Lansing     |         | 3630 |    |        |        |            |
| Mississippi |         | 4366 |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 4373' to 4350' and ran 5 sacks of cement. Mudded 1500' of casing and then circulated casing with 25 sacks of Aquagel mud. Set a rock bridge at 250' and ran 20 sacks of cement. Mudded the hole to 35', set a 5' rock bridge and ran 10 sacks of cement on top. Plugging completed.

10-10-55

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Oklahoma, COUNTY OF Key, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Shelia Wellborn*

Box 791 Ponca City, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1955

*Katherine Hinton*  
Katherine Hinton - Notary Public.

My commission expires November 12, 1957



ROTARY DRILLING LOG

OPERATOR: O. H. Parker  
Campbell #1  
SW NW SW Sec. 31-31S-8W  
Harper County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 4/7/55  
COMP: 4/25/55

| <u>Formation</u>     |      |
|----------------------|------|
| Sand, Clay & Red Bed | 40   |
| Shale & Shells       | 70   |
| Red Bed & Shale      | 120  |
| Red Bed & Shells     | 205  |
| Red Bed & Shale      | 650  |
| Shale & Shells       | 1315 |
| Anhydrite            | 1340 |
| Shale & Lime         | 2680 |
| Shale & Broken Lime  | 2775 |
| Lime & Shale         | 3499 |
| Sand                 | 3545 |
| Sandy Lime & Shale   | 3620 |
| Lime & Shale         | 3705 |
| Lime                 | 4188 |
| Lime & Shale         | 4308 |
| Lime                 | 4351 |
| Lime & Shale         | 4373 |
| Rotary Total Depth   | 4373 |

Remarks  
Set 8-5/8" casing at 252' cemented with 175 sacks pozmix

Set 5-1/2" casing at 4367' cemented with 100 sacks pozmix.

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*  
R. R. McNicol

RECEIVED  
OIL CORPORATION COMMISSION  
9-22-55  
SEP 22 1955

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 31 T 31 R 8W  
BOOK PAGE 2 LINE 33