

15-077-30159-00-00

WELL PLUGGING RECORD  
K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

RECEIVED

AUG 14 2002  
8-14-02  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER \_\_\_\_\_  
Drilled in "66 \_\_\_\_\_  
LEASE NAME Carr A \_\_\_\_\_  
WELL NUMBER 1 \_\_\_\_\_  
990 \_\_\_\_\_ ft. from S Section Line  
1650 \_\_\_\_\_ ft. from E Section Line  
SEC. 31 TWP. 31S RGE. 8W (E) or (W) \_\_\_\_\_  
COUNTY Harper \_\_\_\_\_  
Date Well Completed 1966 \_\_\_\_\_  
Plugging Commenced 2/13/02 \_\_\_\_\_  
Plugging Completed 2/15/02 \_\_\_\_\_

LEASE OPERATOR R & B Oil & Gas, Inc.  
ADDRESS PO Box 195, Attica, KS 67009  
PHONE # (620) 574-7251 OPERATORS LICENSE NO. 31191  
Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)  
The plugging proposal was approved on 2/13/02 (date)  
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us R & B Oil doesn't have

Producing Formation Mississippi Depth to Top Info Not Avail. Bottom Info Not Avail. T.D. 4346  
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	209	none
Mississippi	Oil & Gas	Unknown	Unk.	4 1/2	4336	2841

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Sand at 4254, baled 4 sacks cement. Shot pipe at 3019, 2841, came free. Pulled to 1200, pumped 35 sacks cement. Pulled to 800, pumped 345 sacks cement. Pulled to 260, pumped 75 sacks cement. Circulated cement to surface and pulled rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.  
STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry, Pres. of R & B Oil & Gas, Inc. (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Randy Newberry  
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 11th day of August, 2002

Rebecca S Newberry Notary Public



My Commission Expires: 7-21-2005

OK

# - ALLIED CEMENTING CO., INC. 09038

Federal Tax I.D.# 48-0727860

TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge*

**15-077-30159-0000**

DATE <i>2-15-02</i>	SEC. <i>31</i>	TWP. <i>31S</i>	RANGE <i>8W</i>	CALLED OUT <i>6:00 A.M.</i>	ON LOCATION <i>9:30 A.M.</i>	JOB START <i>10:00 A.M.</i>	JOB FINISH <i>11:30 A.M.</i>
LEASE <i>Camp A</i>		WELL # <i>#1</i>		LOCATION <i>Mag Plant 4S 3/4W</i>		COUNTY <i>Harper</i>	STATE <i>Ks,</i>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				Sinto			

CONTRACTOR *Quality Well*

TYPE OF JOB *O.H.P.*

HOLE SIZE *7 7/8* T.D. *1200*

CASING SIZE *4 1/2* DEPTH *1200*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT *Fresh H<sub>2</sub>O*

EQUIPMENT

OWNER *R+B Oil + Gas*

CEMENT AMOUNT ORDERED *\$50sx 60'40'4*

COMMON	<i>90</i>	@ <i>6.65</i>	<i>598.50</i>
POZMIX	<i>60</i>	@ <i>3.55</i>	<i>213.00</i>
GEL	<i>5</i>	@ <i>10.00</i>	<i>50.00</i>
CHLORIDE		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<i>155</i>	@ <i>1.10</i>	<i>170.50</i>
MILEAGE	<i>155 x 23</i>	<i>.84</i>	<i>142.60</i>
TOTAL			<i>1174.60</i>

RECEIVED  
AUG 14 2002  
8-14-02  
KCC WICHITA

**REMARKS:**

**SERVICE**

*Pump 35sx at 1200 FT Displace  
w/1100lb pump 35sx at 800 FT  
Displace w/1100lb water  
at 300 FT Circ Cement to  
surface w/75 sx wash up  
Rig Down*

DEPTH OF JOB *1200*

PUMP TRUCK CHARGE *475.00*

EXTRA FOOTAGE @

MILEAGE *23* @ *3.00* *69.00*

PLUG @

TOTAL \_\_\_\_\_

CHARGE TO: *R+B Oil + Gas,*

STREET *P.O. Box 195*

CITY *ATTECA* STATE *KANSAS* ZIP *67009*

**FLOAT EQUIPMENT**

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX *109.99*

TOTAL CHARGE *1828.59*

DISCOUNT *171.86* IF PAID IN 30 DAYS

*1656.73*

SIGNATURE *Richard O. McIntyre*

*Richard O McIntyre*  
PRINTED NAME