

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-077-20015-0000
 API NUMBER None issued

LEASE NAME CARR 'B'

WELL NUMBER #1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 31 TWP. 31S RGE. 8W ~~XX~~ or (W)

COUNTY Harper

Date Well Completed 3/25/85

Plugging Commenced 3/25/85

Plugging Completed 3/25/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MULL DRILLING COMPANY, INC.

ADDRESS P.O. Box 2758, Wichita, KS 67201

PHONE#(316) 264-6366 OPERATORS LICENSE NO. 5155

Character of Well Depleted - non commercial

(Oil, Gas, [D&A,] SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve VanGieson

Is ACO-1 filed? this date If not, is well log attached? on file

Producing Formation P&A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		surf	248'	8-5/8"	241'	None pulled
				4-1/2"	4372'	None pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

3/25/85

Pumped 50 sx cement, displaced w/50 BW, down 4 1/2" csg on bottom. Pumped 2 gal on top

of anchor catcher. Ran 1" pipe down to anchor catcher. Pumped 15 sx in 4 1/2" on top.

Circ to surf. Plld 1". Ran 1" to 277'. Pmpd 10 sx gel, 200# bulls fld w/1 jt pipe. Pmpd

(If additional description is necessary, use BACK of this form.)

60 sx cement in surf pipe. Circ to top. P&A 3/25/85 5:00 PM

Name of Plugging Contractor Mull Drilling Company, Inc. LICENSE # 5144

STATE CORPORATION COMMISSION

Address P.O. Box 2758, Wichita, Kansas 67201

STATE OF Kansas COUNTY OF Sedgwick

MAY 06 1985
 5-6-85

Michael R. Kidwell, President (Employee of Conservation Division Operator) of above-described well, being first duly sworn on oath, says: That I have a knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael R. Kidwell

(Address) P.O. Box 2758, Wichita, KS67201

SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 85

Patricia L. Ungleich
 Notary Public
 Patricia L. Ungleich



15-077-20015-0000

#1 CARR "B"

Mull Drilling Company

Total depth: 4380'

Elevation: 1550 KB 1545 GL

Contractor: Donelson Drilling Co.

Location: 132' NE of C NW NW
Sec. 31-31S-8W

Commenced: 4/9/67

Harper County, Kansas

Completed: 4/18/67

Casing Record: 241.37' 8 5/8"
set @ 248.37' w/175 sks.

Formation:

Depth:

Surface hole

250'

Shale

1380'

Lime & Shale stks.

1535'

Lime & Shale

2386'

Shale

2640'

Shale & Lime

2840'

Shale

3018'

Lime

3165'

Shale & Lime

3413'

Shale

3490'

Sand & Shale

3561'

Lime & Shale

3650'

Lime

3745'

Lime & Shale

3790'

Lime

4150'

Lime & Shale

4357'

Chert

4380' TD

RECEIVED
STATE CORPORATION COMMISSION

MAY 06 1967
5-6-85
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

James L. Donelson
James L. Donelson

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 20 th day of April, 1967.

Lorely L. Scott
Notary Public

My Commission expires: April 16, 1969