

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAP 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Venus Oil Company  
Complete Address 1200 N.B.C. Bldg., San Antonio, Texas 78205  
Lease Name Iris Well No. 1  
Location C SE SW Sec. 11 Twp. 34 Rge. 31 (~~EX~~) (W)  
County Seward Total Depth 6030'  
Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated None  
Plugging Contractor Sargents Casing Pulling Co.  
Address Box 506, Liberal, Kansas License No. 511  
Operation Completed: Hour 4:00PM Day 16 Month 3 Year 1972

The above well was plugged as follows:

8 5/8" to 1555' circulated w/ cement. 5 1/2" to 6030' cemented.  
Top perforations 3024' Plug bottom w/ 25 sacks cement 2800'  
Top of cement 2800' Mud 2800' to 1580'  
Spotted 35 sacks cement 1580' to 1480' Mud 1480' to 45'  
Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump  
Pulled 2483' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3-23-72

INV. NO. 5390-W