

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1973

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frontier Oil Company  
 Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202  
 Lease Name Brack "A" Well No. 1  
 Location SE NE NE Sec. 34 Twp. 17 Rge. (E) (W) 16  
 County Rush Total Depth 3670'  
 Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
 Other well as hereafter indicated         
 Plugging Contractor Knight Casing Pulling Co.  
 Address Box 405 Chase, Kansas 67524 License No. ~~XX~~ 436  
 Operation Completed: Hour 9 A Day 7 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3670' 8 5/8 csg set at 201' cwc 160 sk.

4 1/2 csg set at 3409' cw 185 sk cem.

4 1/2 csg FBTD 3040' with perf. (2995-3001)

Filled 4 1/2 csg W/sd (2950-3040) dumped 3 sk cem W/dump bailer. (2915-2950)

Cutoff and recovered 520' of 4 1/2 csg.

Pumped down 8 5/8 csg with 10 sk gel & water W/200 lbs hulls -- released 8 5/8 plug  
 and pumped 120 sk 50-50 poz cem. W/2% total gel. Max PP 1000# SIP 450#

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. R. [Signature]  
Well Plugging Supervisor

DATE 11/9/73

INV. NO. 8143-113