

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22586-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name V. Francis Weigel

Complete Address Box 244, Gorham, Kansas 67640

Lease Name Chesney "B" C Well No. #51

Location Center of E/2-SE-SE Sec. 6 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Shields Drilling Co., Inc.

Address Shields Bldg, Box 709, Russell, Kansas 67665 License No. _____

Operation Completed: Hour: 12:30PM Day: 7th Month: Oct. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8"-209' sp. w/165 sacks common-2% Gel-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem, with heavy mud between all plugs.

1st plug @ 810' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole and 5 sacks of cement in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION
10-13-81
OCT 13 1981

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

11-25-81
8506-U

CONSERVATION DIVISION
Wichita, Kansas