

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -077-20496-0000 (of this well)

Operator's Full Name Cities Service Co.
 Complete Address 700 Sutter Pl, Bldg, 209 E-Wm. Wichita, Ks 67202
 Lease Name Leeper "A" Well No. 1
 Location SW-NW Sec. 23 Twp 31 Rge. 8 (E) (W) W
 County Harper Total Depth 4492
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated _____
 Plugging Contractor Felso Casing Pulling
 Address Box 176 Chase, Kans License No. 683
 Operation Completed: Hour 2:45 pm Day 2 Month 3 Year 1979

The above well was plugged as follows:

245'-8 5/8" casing w/ 225 sac cement - 5 1/2" casing set @ 4488'
w/ 200 sac cement - Top of prof 4400' & 4410' sand back to 4300'
top sand w/ 5 sac mixed cement w/ dump bailer - pull
3505'-5 1/2" casing - three mixed & pumped 5 sac bulls
20 sac gel-release plug mixed & pumped 100 sac 50/50
perm cement w/ 27 gal - 37 cc to top of casing shut
in w/ 700# pressure

RECEIVED
STATE CORPORATION COMMISSION

MAR - 5 1979

3-5-79

I hereby certify that the above well was plugged as herein stated

INVOICED

DATE 3-7-79

INV. NO. 9216. W

Signed: [Signature]
 Well Plugging Supervisor
 CONSERVATION DIVISION
 Wichita, Kansas