

15-077-20017-0000

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1967

5-1-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed April 18, 1967.

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Squire Well No. # 2

Location C SE SW Sec. 26 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4802'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:00PM Day 29th Month April Year 1967

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 240'. 1st cementing plug, bridged with
1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented
with 35 sacks, through the drill pipe. Hole was filled with drilling
mud to 60', 2nd cementing plug, bridged with 1/2 sack of Gel-Mud and 1/2
sack of hulls on fluid at 60', and cemented with 25 sacks. Rat and mouse
holes bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 5/2/67

INV. NO. 5146-W