

15-195-33071-0001

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Hellar Drilling Company, Incorporated,

Complete Address: 1014 Union Center, Wichita, Kansas.

Lease Name Keller Well No. 1-W

Location NE/4 Sec. 9 Twp. 13 Rge. (10) (10) 21

County Trego Total Depth 3887

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:00M Day 14 Month 9 Year 1966

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated.
3887'--5 1/2" casing. (No amount of cement indicated) Well converted to use
as salt water disposal. Perforations from 1060' to 1100'.

Checked bottom with bailer. Found bottom @ 1100'. Set 5 sacks cement
@ 1100' with dump bailer. Pulled 5 1/2" casing and squeezed well with 40
sacks gel followed with 100 sacks cement. Pump-in pressure 250#. Final
shut-in pressure 100#. (Recovered 1100' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 9/20/66
INV. NO. 3753-W