

15-195-33072-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Glen Armour dba Western Oil Field Service,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name Kellar Well No. 2

Location N $\frac{1}{2}$ -NE Sec. 9 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3890

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling Company.

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 3:30PM Day 26 Month 12 Year 1964

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated. 3887'--4 1/2" Production casing cemented with 50 Sx. Well plugged back to 3885'. Top perforations @ 3878'.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer.

Squeezed hole with 30 Sx. gel followed with plug and 50 Sx. cement.

Final shut-in pressure 100#. (Recovered 350' 4 1/2" casing)

(Mudding and cementing operations performed by Globe Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

DATE 12/21/64

INV. NO. 438-W

Signed: W. D. Nichols  
Well Plugging Supervisor