

15-195-00259-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Glen E. Amour (dba) Western Oil Field Service,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name Keller Well No. 1

Location N/2-NE Sec. 9 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3959

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 6:00PM Day 23 Month 12 Year 1964

The Above well was plugged as follows:

215'--8 5/8" surface pipe, cement circulated. 3958'--5 1/2" Production casing cemented in with unknown amount of cement. Well plugged back to 3919'. Top perforations @ 3890'. Well squeezed in the Dakota Sands.

Sanded well back to 3875' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" to 600' and circulated heavy gel mud (used 30 Sx. gel). Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/28/64

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 415-W

INVOICED