

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-9-70
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl. Bank Bldg. Wichite, Ks 67202

Lease Name Asper Well No. 1

Location SE/SW/SW Sec. 29 Twp. 31 Rge. 8 (E) (W) X

County Harper Total Depth 4356

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 2:00PM Day 6 Month 2 Year 1970

The above well was plugged as follows:

210 ft 8 5/8 surface pipe cemented with 155 sacks cement. 4347 ft of
5 1/2 long string cemented with 125 sacks. 2% gel. 3470 ft of 5 1/2
pulled. Open hole completed Sand 4300 ft, 5 sacks cemented with
bailer. Fill hole to 205 ft, 10 ft rock bridge, 25 sacks cement.
Mud to 40 ft, 10 ft rock brdige. 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell Bilenstein
Well Plugging Supervisor

DATE 2/9/70
INV. NO. 1397-W