

15-877-2003-0000

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-26-68
JAN 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 23, 1968.

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name Hostetler "A" Well No. # 1

Location C W/2 SW SE Sec. 29 Twp. 31 Rge. 8 (E) (W)W

County Harper Total Depth 4377'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 3:00PM Day 25th Month January Year 1968

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cemented with 165 sacks. 4373' of 4 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the hole
was sanded to 4350', and cemented with 4 sacks, through the dump bailer,
with cement from 4350' to 4300'. 3704' of 4 1/2" long string was recovered
from the hole. Hole was filled with mud to 205', rock bridge from 205'
to 195', and cemented with 25 sacks, with cement from 195' to 120'. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with
10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/68
INV. NO. 4150-U

Signed: Audie Elving
Well Plugging Supervisor