

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1972
9-11-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.
Complete Address 705 4th Natl Bldg. Wichita, Ks
Lease Name Broce B Well No. 1
Location SE/SE/NW Sec. 29 Twp. 31 Rge. 8 (E) (W) W
County Harper Total Depth 4398
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling Co. Inc.
Address Box 1082 Great Bend, Ks License No. 623
Operation Completed: Hour 10:00 AM Day 9 Month 9 Year 1972

The above well was plugged as follows:

204 ft 8 5/8 surface pipe cemented with 145 sacks. 4389 ft 4 1/2 long
string cemented with 125 sacks. Open hole. Sand to 4375 ft. Four
sacks cement with bailer. Pulled 3500 ft 4 1/2. Set 10 ft rock bridge
at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Bickert
Well Plugging Supervisor

DATE 9/12/72
INV. NO. 6293-W