

*116*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 10 1964  
2-10-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Wm. L. Carr Well No. # 3

Location SE NE SW Sec. 30 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4385

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 5:00PM Day 8th Month Feb. Year 1964

The Above well was plugged as follows:  
230' of 9 5/8" surface pipe, cemented with 250 sacks. 4373' of 5 1/2" long  
string, cemented with 200 sacks. Plug back to 4369'. Top perforation 4362'.  
Bottom of the hole was sanded to 4350', and cemented with 5 sacks. Hole  
was filled with mud to 270', with 10' rock bridge, and cemented with 35  
sacks, bringing the cement to 215' in the surface pipe. Hole was filled  
with mud to 40', with 10' rock bridge, and cemented with 12 sacks to  
base cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 2/11/64  
INV. NO. 8610-11

Signed: Archie Elving  
Well Plugging Supervisor