

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

FEB 7 1964

2-7-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.  
 Complete Address: 300 N. Broadway, Wichita, Kansas  
 Lease Name Wm. L. Carr Well No. # 2  
 Location C S/2 SW SW Sec. 30 Twp. 31 Rge. 8 (E) (W) W  
 County Harper Total Depth 4375  
 Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
 Other well as hereafter indicated:       
 Plugging Contractor: Ace Pipe Pulling Co.  
 Address: Box 304, Great Bend, Kansas License No. 2  
 Operation Completed: Hour 9:30AM Day 6th Month Feb. Year 1964

The Above well was plugged as follows:

254' of 9 5/8" surface pipe, cemented with 250 sacks. 4363' of 5 1/2" long  
string, cemented with 200 sacks. Bottom of hole was sanded to 4350', and  
cemented with 5 sacks. Hole was bailed down to 270'. Plug was set at 270',  
bridged with 10' of rock, and cemented with 30 sacks, bringing the top  
of the cement to 230' in the surface pipe. Hole was filled with mud to  
40', 10' rock bridge, and cemented with 12 sacks to base cellar.  
3142' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

2/9/64

INV. NO.

8602-W

Signed:

Archie Elving  
Well Plugging Supervisor