

15-077-10163-0000

Form CP-3
Rev. 6-26-62

TC
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1965
7-23-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Wasbon Well No. # B-1

Location NE ^{NE} NW NW ^{ANB} ^{CC} Sec. 30 Twp. 31 Rge. 8 (E) (W)W

County Harper Total Depth 4407'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No.

Operation Completed: Hour 4:00 PM Day 21st Month July Year 1965

The Above well was plugged as follows:

206' of 8 5/8" surface pipe, cement circulated. 4407' of 5 1/2" long string,
cemented with 100 sacks. Plug back to 4389'. Top perferation 4331'. Bottom
of the hole was sanded to 4300', and cemented with 5 sacks. 3710' of 5 1/2"
long string was recovered from the hole. Hole was filled with mud to 220',
bridge plug set at 220', and 10' of rock bridge, and cemented with 25
sacks. Hole was filled with mud to 40', and 10' of rock bridge, and cem-
ented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/26/65
INV. NO. 1515-W

Signed: Archie Elving
Well Plugging Supervisor