

6060019

15-051-22, 753-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

ART NUMBER 15-

SE, Sec. 26, T 12 S, R 26 W 18

2310 feet from S section line

1690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Oswald. Well # 1

Operator: Kelso Casing Pulling
Name & Address: Box 347, Chase, Mo. 67524

County Ellis

Well Total Depth 3440 feet \$111.80

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Mo. 67524

Company to plug at: Hour: 3:00 PM Day: 19 Month: 9 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 sh. 50 pozmix - 4 7/8" set - 3 7/8" Cal. Cl., 5 hulls, 20 sh. Gel, & 8 5/8" plug.

Signed Pat G. Schab.
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 PM Day: 19 Month: 9 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 208' w/ 165 sh. 4 1/2" set at 3435' w/ 100 sh. 5' of open hole. Plugged bottom w/ 4 sh. cement, sand & 4 sh. cement to 3400'. Shot pipe 1 time & recovered 2881'. Pumped in 8 5/8" - 4 sh. hulls, 25 sh. cement, 10 sh. Gel, 70 sh. cement, 10 sh. Gel, 1 sh. hulls, released plug & followed w/ 70 sh. cement w/ 700 pounds pressure.

Remarks: By Allied Cementing

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 10-7-83
INV. NO. 5657-W

Signed Pat G. Schab. ✓
(TECHNICIAN)