

1 060573

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,300-0000 *R*

NE NE NE, SEC. 36, T 17 S, R 16 *WXX*

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9609

Lease Name Axman Well # 2-36

Operator: HDR Production, Inc.

County Rush *119.12*

Name & Address 1391 Carr Street, Suite 311

Well Total Depth 3665 (Arbuckle) feet

Lakewood, CO 80215

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 7:00 pm Day: 21 Month: May Year: 19 85

Plugging proposal received from Steve Dunham

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1070-93
Elevation 2000'

1st plug at 1080' with 50 sx cement

2nd plug at 640' with 70 sx cement

3rd plug at 335' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:00 pm Day: 21 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1080' with 50 sx cement, 2nd plug at 640' with 70 sx

cement, 3rd plug at 335' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this report)

INVOICED

DATE 6-6-85

Signed Paul A. Luthi (TECHNICIAN)

INV NO. 8364