

To: 1 052050
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-165-21,653 -0000
C SW, SEC. 34, T 17 S, R 16 W/E
1320 feet from S section line
1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT 6-14
Operator License # 3456
Operator: AFG Energy Inc.
Name:
Address: P.O. Box 458
Hays, KS 67601

Lease Name Scheck Well # 1
County Rush 117.00
Well Total Depth 3600 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1124

Abandoned Oil Well Gas Well X Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Paramount Casing Crews License Number
Address P.O. Box 861, Hays, KS 67601-0861

Company to plug at: Hour: 12 p.m. Day: 14 Month: 6 Year: 19 96

Plugging proposal received from Terry Piesker
(company name) AFG Energy Inc. (phone) 913-625-6374
were: 4 1/2" at 3599' w/200 sx cement, PBDT 3564', Perfs at 3501.5-3504.5, 3471.5-3474.5'

- 1st plug sand back to 3425' and dump 4 sx cement on top of sand through bailer.
- 2nd plug at 1130' with 5 sx gel, 50 sx cement, and 8 sx gel,
- 3rd plug at 600' with 25 sx cement,
- 4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15 p.m. Day: 14 Month: 6 Year: 19 96

- ACTUAL PLUGGING REPORT 1st plug sanded back to 3425' and dumped 4 sx cement on top of sand through bailer,
- 2nd plug at 1130' with 5 sx gel, 50 sx cement, and 8 sx gel,
 - 3rd plug at 600' with 25 sx cement,
 - 4th plug at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2420' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (crossed out) Reserve this plugging.

DATE 6-25-96

Signed Richard W. Lucas (TECHNICIAN)

WIZ. NO. 45871 AUG 20 1996

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1996
CONSERVATION DIVISION
WICHITA, KS