

1050281

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,230 -0080

SE SW NE, SEC. 34, T 17 S, R 16 WXB
2310 feet from N/S section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Brack "A" Well # 4

Operator: Frontier Oil Company
Name & Address: 1720 Kansas State Bank Building
Wichita, KS 67202

County Rush

Well Total Depth 3519 114.37 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:30 pm Day: 6 Month: July Year: 19 84

Plugging proposal received from Walt Oden

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1050' with 50 sx cement

2nd plug at 540' with 40 sx cement

3rd plug at 300' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:00 pm Day: 6 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement, 2nd plug at 540' with 40 sx

cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied

(If additional description is necessary, use BACK of this form.)

(If not) observe this plugging.

INVOICED

DATE 7-16-84

INV. NO. 2545

7-6

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1984

CONSERVATION DIVISION
Wichita, Kansas