

1052342

TO: STATE CORPORATION COMMISSION

API NUMBER 15-033-21,031

0000

110'S S/2 NW NW SEC. 19, T 33 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 1100 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

10-9

LEASE NAME BAKER FARMS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE

198-77

OPERATOR LICENSE # 5086

WELL TOTAL DEPTH 6116 FEET

OPERATOR: PINTAIL PETROLEUM, LTD. PRODUCTION CSG: SIZE @ WITH SX

NAME AND ADDRESS 225 N MARKET, SUITE 300 WICHITA, KS 67202 SURFACE CASING: SIZE 8 5/8" @ 678' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PICKRELL DRILLING CO., INC LICENSE NUMBER 5123

ADDRESS 110 N MARKET, SUITE 205, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 09 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE

(COMPANY NAME) PICKRELL DRILLING (PHONE) 316-262-8427

WERE:

INVOICED

1ST PLUG AT 1000' WITH 50 SX CEMENT.

DATE 10-26-99

2ND PLUG AT 700' WITH 50 SX CEMENT.

WELL NO. 60762

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 09 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1000' WITH 50 SX CEMENT.

2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED KANSAS CORP COMM 1999 OCT 18 1:55 PM

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED

Richard W. Lacey (TECHNICIAN)

FORM CP-2/3

Handwritten signature and initials