

1052283

15-165-21044-00-00

TO:

8-10

API NUMBER

~~165-20644-0000~~

STATE CORPORATION COMMISSION

NW SW NW, SEC. 6, T 16 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WERTH WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY RUSH 38.48

OPERATOR LICENSE # 31521

WELL TOTAL DEPTH 1184 FEET

OPERATOR: KENMARK CORPORATION

PRODUCTION CSG: SIZE 4 1/2" FEET 758

NAME AND P.O. BOX 572

SURFACE CASING: SIZE 8 5/8" FEET 150

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-21,691 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY INC. LICENSE NUMBER NA

ADDRESS P.O. BOX 31 RUSSEL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 10 MONTH: 8 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM BILL LEIKAM

(COMPANY NAME) ALLIED CEMENTING COMPANY (PHONE) 785-483-2627

WERE: CIBP AT 700' PERFORATIONS AT 672' TO 686' PERMANENT PACKER SET @ 665'

PUMP DOWN TUBING STRING WITH 10 SX OF CEMENT AND DISPLACE TO 660' CUT TUBING STRING

LOOSE AT 660' PUMP CEMENT DOWN TUBING STRING CIRCULATING CEMENT BACK TO SURFACE UP 4 1/2"

PULL TUBING STRING AND TOP OFF WELL WITH CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 10 MONTH: 8 YEAR: 98

ACTUAL PLUGGING REPORT ATTEMPTED TO RUN SINKER BAR DOWN TUBING AND COULD NOT GET PASS

320'. HOOKED CEMENT PUMP TRUCK ONTO TUBING TO CLEAR TUBING. STARTED PUMPING AND CIRCULATED

UP THE 4 1/2" CASING. PUMPED A MARKER DOWN THE TUBING AND FOUND TUBING WAS GOOD TO 660'

TUBING PROBABLE HAD THE PACKER REMOVED! PUMPED CEMENT DOWN THE TUBING CIRCULATING IT BACK TO

SURFACE UP THE 4 1/2" CASING USING 40 SX OF CEMENT. CLOSED 4 1/2" CASING AND SQUEEZED 2 SX

OF CEMENT DOWN THE WELL WITH A ISIP OF 500#.

REMARKS: 60/40 6% BY ALLIED CEMENTING 660' OF 2 3/8" FIBERGLASS TUBING LEFT IN THE HOLE.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID OBSERVE THIS PLUGGING.

SIGNED

Richard W. Lacy
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE

8-21-98

WV. NO.

51183

8-10

JAN 29 1999