

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-29

2-070791

API Number: 15-077-21,181-0000

NE-NE-NW
NW-NW-NW

SECTION 27 TWP 31 RANGE 08W

OPERATOR LICENSE 31191
OPERATOR R & B OIL AND GAS INC.
NAME & ADDRESS 904 N. LOGAN BOX 195
ATTICA, KS 67009

4950 FEET FROM S SECTION LINE
2970-4950 FEET FROM E SECTION LINE
LEASE NAME MUIR #1
COUNTY HARPER
WELL TOTAL DEPTH 4304' 139.88
PIPE 4 1/2" @ 4425'
SURFACE CASING 8 5/8" @ 250'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: P.O. BOX 333, ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: _____ HOUR: 1:00 DAY: 29 MONTH: 9 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: (316) 254-7893

WERE: SET C.I.B.P. @ 4000' AND 5 SACKS
35 SACKS @ 1200
35 SACKS @ 800
300' TO 0'

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL X PART _____ NONE _____

COMPLETED: HOUR: 5:00 DAY: 29 MONTH: 9 YEAR: 1998

ACTUAL PLUGGING REPORT: SET C.I.B.P. @ 4000' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 3000'.
PULLED TO 1200'. PUMPED 35 SACKS. PULLED TO 800'. PUMPED 35 SACKS. PULLED TO 300'. CIRCULATED CEMENT
TO SURFACE.

REMARKS: ALLIED #2542, 60/40 POZ, 4% GEL.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 07 1998
10-7-98
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

INVOICED

DATE 10-8-98
INV. NO. 51428

FORM CP-2/3
REV. 3/90

9-29 JAN 29 1999