

2 040287

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077 -20920-0000

nw/5w/nw, SEC. 28, T. 31 S, R. 8

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # SK16

Lease Name Reid Well # 1

Operator: Rains & Williamson

County Harper 143.16

Name & Address 435 Page Court 220 W Douglas

Well Total Depth 4905 feet

Wichita Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well + Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Company Tools License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Jack Davis

(company name) Rd W (phone) \_\_\_\_\_

were: \_\_\_\_\_

5 1/2 4401 sand to 4350 & 5sk

OH 4401-05 3 Hull 15 gel 65 sk

Plugging Proposal Received by St. Vanden  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 1100 Day: 2 Month: 5 Year: 1986

ACTUAL PLUGGING REPORT sand was dumped in the well 50' above the bottom of the pipe at 4350' and capped with 5sk of cement. The 5 1/2 was shot off and recovered from 2900'. The Top was squeezed plugged thru the 8 5/8 3 sks of hulls, 15 sks of gel & 65 sks of Pozmix cement

Remarks: BJ Titan RECEIVED MX 700 SI 300

(If additional description is necessary, use BACK of this form.)

INVOICED  
AUG - 7 1986

observe this plugging.

Signed St. Vanden  
(TECHNICIAN)

DATE \_\_\_\_\_

INV. NO. 14665

AUG 7 1986