

9-25

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-20 566 20965-0000
JR-RCC

200' N C NE NW, SECTION 29 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5123 4820 FEET FROM S SECTION LINE
OPERATOR PICKRELL DRILLING COMPANY INC 3960 3300 FEET FROM E SECTION LINE
NAME & 110 NORTH MARKET #205
ADDRESS WICHITA, KS 67202

LEASE NAME: BROCE AB #5
COUNTY: HARPER *142.94*
WELL TOTAL DEPTH: 4389' 4398
PIPE: 5 1/2" @ 4389'
SURFACE CASING: 8 5/8" @ 211'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION

ADDRESS: MEDICINE LODGE, KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DON AUMILLER

COMPANY NAME: PICKRELL DRILLING INC PHONE: _____

WERE: OH 4389-98' 35 SACKS AT 1350'
35 SACKS AT 900'
CIRC 275' TO SURF

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:30 DAY: 25 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: THE ~~OFF~~ WAS FILL WITH SAND FROM 4398' TO 4330' AND CAPPED WITH 5 SACKS OF CEMENT. PIPE WAS PULLED FROM 3000'. TUBING RAN TO 1350' WHERE 35 SACKS OF CEMENT WAS SPOTTED. TUBING PULLED TO 900' WHERE 35 SACKS OF CEMENT WAS SPOTTED. TUBING WAS PULLED TO 285' AND CEMENT WAS CIRCULATED TO SURFACE.

REMARKS: _____

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 28 1997
~~10-28-97~~
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING

[Signature]
STEVE VAN GIESON

INVOICED

DATE OCT 29 1997

INV. NO. 49379