

1-15

2-100691

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21,231-0000

C NE NE NE, SECTION 29 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6581 4950 FEET FROM S SECTION LINE
390 FEET FROM E SECTION LINE

OPERATOR Bison Energy Corp
NAME & Box 782317
ADDRESS Hutchinson, KS 67278

LEASE NAME: Wiley #1-29
COUNTY: Harper
WELL TOTAL DEPTH: 4430' 143.97

CONDUCTOR PIPE: _____
SURFACE CASING: 8-5/8" @ 225'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Lobo Drilling Company
ADDRESS: Box 877, Great Bend, KS 67530 LICENSE: 5864

COMPANY TO PLUG AT: HOUR: 8:00p DAY: 15 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Erwin Neighbors
COMPANY NAME: Bison Energy PHONE: _____

WERE: 25 sx 1500' - 25 sx @ 900' - 35 sx @ 275' - 25 sx @
60' 10 sx R.H. - 10 sx M.H. - 5 sx W.W.

PLUGGING PROPOSAL RECEIVED BY: Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 9:00p DAY: 15 MONTH: 1 YEAR: 1991

ACTUAL PLUGGING REPORT:
Filled hole w/mud - pulled drl pipe to 1500' - spotted
25 sx cmt - pulled pipe to 900' - spotted 25 sx of cmt
- pulled pipe to 275' & spotted 35 sx cmt - pulled pipe
to 60' - circ 25 sx cmt to surf - put 10 sx in rat hole
- 10 sx in mouse - 5 sx in water well.

REMARKS: B. J. Service #636457 C1 "A"

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

John L. Sanders
J. L. Sanders (AGENT)

DATE 4-5-91 4-4-91 APR 4 1991

INV. NO. 31352
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

pw