

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-20,901-0000

SW SW NW, SECTION 8 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5923 FEET FROM S SECTION LINE 2970
OPERATOR AMERICAN PETROLEUM COMPANY INC. FEET FROM E SECTION LINE 4950
NAME & HCR 69, BOX 413-2
ADDRESS SUNRISE BEACH, MO 65079
LEASE NAME: DICKSON #4
COUNTY: HARPER
WELL TOTAL DEPTH: 4520' 146.90
PIPE:
SURFACE CASING: 8 5/8" @ 208'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: CLARKE CORPORATION

ADDRESS: MEDICINE LODGE, KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: ALAN VITRAL

COMPANY NAME: CLARKE CORPORATION PHONE: (316) 886-9855

WERE: 4 1/2" @ 4532' 35 SACKS AT 1450'
PBDT 4473' 35 SACKS AT 950'
PERFS 4400-14' CIRC. 260'

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 04 1997
3-4-97

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 13:00 DAY: 17 MONTH: 2 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 4413' TO 4350' AND CAPPED WITH 4 SACKS OF CEMENT. THE 4 1/2" WAS RECOVERED FROM 3400' AND PULLED TO 1463' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 931' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE 4 1/2" WAS PULLED TO 280' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING CASING PULLED AND CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

INVOICED

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson

STEVE VAN GIESON

DATE

INV. NO. 47691