

6-8

2-040632

253

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,904 - 0000

C NE SW, SECTION 21 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 1980 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.
NAME & 110 S. Main, #500
ADDRESS Wichita, KS 67202

LEASE NAME: Burgess #C-1
COUNTY: Harper 143.00
WELL TOTAL DEPTH: 4400'

RECEIVED
STATE CORPORATION COMMISSION

III 2 1991
7-291
CONSERVATION DIVISION
Wichita, Kansas

CONDUCTOR PIPE: " @ '

SURFACE CASING: 8-5/8" @ 265'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson
COMPANY NAME: McCoy Petroleum Corp. PHONE: _____

WERE: 5-1/2" 14# @ 4390' w/100 sx - O.H. 4390'-4400' - CIBP
4350' & 2 sx - 35 sx @ 1400' - 35 sx @ 1000' - circ
from 315' .

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 8 MONTH: 6 YEAR: 1991

ACTUAL PLUGGING REPORT:
A CIBP set @ 4340' & capped w/2 sx cmt - 5-1/2" csg
shot loose & pulled to 1427' & 35 sx cmt spotted - 5-
1/2" csg pulled to 1025' & 35 sx cmt spotted - 5-1/2"
csg pulled to 315' where cmt circ to surf - Howco 60/40
- circ hole w/gel from 1400' - rec 3800' of 5-1/2" csg

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

DATE JUL 22 1991

FORM CP-2/3
REV. 3/90

INV. NO. 32338

SEP 27 1991

DW

6-8