

7-15

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
203 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-20978-0000

N/2 SW SW, SECTION 21 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 990 FEET FROM S SECTION LINE  
660 FEET FROM W SECTION LINE

OPERATOR McCoy Petroleum Corp.  
NAME & 110 S. Main #500  
ADDRESS Wichita, KS 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

LEASE NAME: Burgress B-4

COUNTY: Harper

WELL TOTAL DEPTH: 4380' 142.35'

AUG 02 1993  
8-2-93  
CONSERVATION DIVISION  
WICHITA, KS

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 264'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Shawnee Well Service

ADDRESS: Attica, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Jana Green

COMPANY NAME: McCoy Petroleum PHONE: 316-265-9697

WERE: 5-1/2 4370', OH 4370-80', Sand back to 4320' & 5sx,  
30sx @ 1350', 30sx @ 900', circ cmt from 310'

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:40 DAY: 15 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:

The perfs were covered with sand from 4380' to 4315'  
and capped with 5sx of cmt- the 5-1/2" was recovered  
from 2800' and pulled to 1369' where 30sx of cmt was  
spotted- the pipe was pulled up to 929' where 30sx of  
cmt was spotted- the pipe was again pulled up to 321'  
where cmt was circ to surface- the remaining pipe was  
pulled from wellbore to fill back to surface with cmt

REMARKS: Allied #1267 60/40 4% gel

I DID OBSERVE THIS PLUGGING.

INVOICED  
AUG 04 1993

DATE \_\_\_\_\_  
INV. NO. 38346

Steve Van Gieson  
Steve Van Gieson (AGENT)