

15-077-20012-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 32 Twp. 31 Rge. (E) 8 (W)

Location as "NE/CNWxSWx" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Warren "B" Well No. 1
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 26, 1966
Application for plugging filed April 26, 1966
Application for plugging approved April 26, 1966
Plugging commenced April 26, 1966
Plugging completed April 26, 1966
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200'. Set plug, cemented with
20 sacks cement. Heavy mud to 40'. Set plug,
cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 - 1966
S-S-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Maxine Blackman, (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well has been filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebils
705 4th National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 28th day of April, 1966



Maxine Blackman
Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 4-12-66

Rotary Drilling Completed 4-25-66

LOCATION: Warren "B" No. 1, C SE NW Section 32-31S-8W, Harper County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (8 jts) 8 5/8" surface casing set at 204', cemented with 145 sacks cement. Circulated. Completed 6:15 P.M. April 12, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Red Rock & Surface Soil	<u>C. F. S.</u>
205	Red Rock	3449
950	Red Bed & Shale	3620
1465	Shale & Shells	3645
3355	Lime & Shale	3925
3331	Heebner	4060
3449	Shale	4340
3620	Shale & Lime	4349
3449	Shale	4361
3620	Shale & Lime	4635
3645	Sandy Lime & Shale	4645
3745	Sandy Lime	4664
3883	Shale & Lime	4671
4010	Lime	4682
4031	Shale	4687
4105	Lime	4693
4305	Lime & Shale	4698
4340	Lime & Mississippi	4750
4349	Miss. Chert	
4430	Mississippi	<u>Slope Tests</u>
4477	Lime	2500
4509	Mississippi	3000
4635	Shale & Lime	3500
4665	Kinderhook	4300
4740	Viola	
4750	Simpson - RTD	<u>S. L. M.</u>
		3200
		3926
		4671

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 - 1966
5-5-66
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY

By [Signature]
C. S. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 28th day of April, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



[Signature]
Maxine Blackman, Notary Public

My commission expires: June 21, 1966