

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 32 TWP. 31S RGE. 8W E/W
Location as in quarters or footage from lines:
C SW NE

		32 ⁺	

Locate Well
correctly on above
Section Platt.

Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name G. V. Smith Well No. 1
Office Address 221 S. Broadway, Suite 400, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed December 17, 1981
Application for plugging filed January 6, 1982
Plugging commenced December 17, 1981
Plugging completed December 17, 1981
Reason for abandonment of well or producing formation
Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4422'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	297'	8-5/8"	292.45'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged with plug and 60 sacks cement at 520';
plug and 40 sacks cement at 290'; 10 sacks cement
and solid bridge plug at 40'; and 10 sacks cement
in rat hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John D. Knightley (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
221 S. Broadway, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 82

Stella J. Lipps
Notary Public.

My Commission expires: March 12, 1983



RECEIVED
1-7-82
7 1982
CONSERVATION DIVISION
Wichita, Kansas

D. R. Lauck Oil Company, Inc. - G. V. Smith #1
 221 S. Broadway, Suite 400 C SW NE Sec. 32-31S-8W
 Wichita, Kansas 67202 Harper County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 221 S. Broadway, Suite 400
 Wichita, Kansas 67202

Commenced: December 8, 1981
 Completed: December 17, 1981

Drillers Log

Red Bed	302
Shale	3100
Shale & Lime	3310
Lime & Shale	3690
Shale & Lime	3865
Shale	4120
Shale & Lime	4235
Lime & Shale	4366
Shale & Lime	4371
Lime	4422 RTD

RECEIVED
 STATE CORPORATE COMMISSION

JAN 7 1982
 1-7-82
 CONSERVATION DIVISION
 Wichita, Kansas