

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper

County. Sec. 8 Twp. 31 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SE

Lease Owner Morgonstern & Specter

Lease Name Fleming

Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 9-14-54 19

Application for plugging filed October 17, 1957 19

Application for plugging approved October 18, 1957 19

Plugging commenced October 21, 1957 19

Plugging completed October 26, 1957 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production September 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Rives

Producing formation Mississippi Depth to top 4392 Bottom 4501 Total Depth of Well 4501 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	175	None
				5 1/2" OD	4502	3687.50ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 4415 up to 4385. Dumped 5 sacks of cement and filled up to 4320. Shot pipe off at 3687 and pulled pipe up to 1800 ft.; had Globe circulate 60 sacks of Controgel mud; pulled pipe out and baled down to 200 ft., set ;0 ft. rock bridge, dumped 25 sacks of cement mud up to 35; rock bridge 10 sacks of cement up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Co.

Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morgonstern & Specter Pipe & Supply (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Morganstern

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1957

My commission expires

March 9, 1958

W. N. Anderson

Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FIL. SEC 8 T 31 R 8W
BOOK PAGE 55 LINE 5

NOV 16 1957
11-16-57
CONSERVATION DIVISION
Wichita, Kansas


15-077-10072-0000
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- SOHIO PETROLEUM CO.
 Farm- Fleming No. 1

SEC. 8 T. 31 R. 8W
 SW NW SE

Total Depth. 4501'
 Comm. 8-31-54 Comp. 9-14-54
 Shot or Treated.
 Contractor. Garvey Drlg. Co.
 Issued. 3-26-55

County Harper
 KANSAS



Elevation. 1628' RB

Production. 30 BO & 68% wtr.

CASING:

8 5/8" 175' cem w/125 sx
 5 1/2" 4502' cem w/150 sx

Figures Indicate Bottom of Formations.

sand & shale	175
shale	350
shale & red bed	575
shale & shells	1500
lime & shale	1700
lime	1875
lime & shale	2105
lime	2310
lime & shale	2640
lime, shells & shale	2790
lime & shale	3045
shale & shells	3110
lime	3165
lime & shale	3270
lime	4125
lime & shale	4401
lime	4486
Cored	4501
Total Depth	

Tops: Scout	
Lansing	3608
Mississippi	4392

PLUGGING
 FILE SEC. 8 T. 31 R. 8W
 BOOK PAGE 55 LINE 5