

15-077-00015-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

T 31S NORTH R 8 W

	21		
		X	

Locate well correctly on above
Section Plat

Harper County. Sec. 21 Twp 31 Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines. NE NW SE

Lease Owner Musgrove Petroleum Corporation

Lease Name BURGESS A Well No. 1

Office Address 801 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Now dry

Date well completed February 20 1956

Application for plugging filed September 10, 1956

Application for plugging approved September 12, 1956

Plugging commenced September 17, 1956

Plugging completed September 20, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production June 30 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Miss. Depth to top 4383 Bottom 4435 Total Depth of Well 4435 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	174'	none
				5-1/2"	4435'	3627

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 4424' to 4370'.
 Ran 5 sx cement.
 Pulled casing up to 1500' and circulated the hole with 68 sacks of jell mud. Mudded the hole to 180', set a rock bridge to 174' and ran 20 sx of cement.
 Mudded the hole to 35', set a rock bridge to 30' and ran 10 sx cement which filled to base of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
 Address Chase, Kansas.

STATE OF Kansas COUNTY OF Sedgwick

I, Gordon L. Koelling (employee of owner) or (owner or proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
 801 Union Center, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of October, 1956

My commission expires June 16, 1959

Dean J. Hefke
 RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public.

PLUGGING
 FILE SEC. 21 T. 31 R. 8W
 BOOK PAGE 98 LINE 1

OCT 4 X 1956
 10-4-56
 CONSERVATION DIVISION
 Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: BURGESS A #1
 LOCATION: NE NW SE, Sec. 21-31-8
 Harper County, Kansas.
 COMMENCED: February 5, 1955
 COMPLETED: February 20, 1955

0	25	Surface soil
25	174	Red bed, shells & shale
174	600	Shale & shells
600	812	Sandy shale
812	1315	Sandy shale & shells
1315	1400	Shale & shells
1400	1480	Shale & lime
1480	1680	Shale & shells
1680	3290	Shale & lime
3290	3338	Sand & shale
3338	3457	Lime & shale
3457	3475	Lime & sand
3475	3535	Shale & lime
3535	3565	Shale & sand
3565	3766	Lime & shale
3766	3855	Sandy shale & lime
3855	4122	Shale & lime
4122	4178	Shale & lime streaks
4178	4222	Shale & hard lime streaks
4222	4256	Lime & shale
4256	4310	Hard lime & shale
4310	4381	Shale & lime
4381	4435	Mississippi lime
	4435	Notary Total Depth

Set 8-5/8" surface pipe at 174' with 165 sacks cement.

Set 5-1/2" pipe at 4435'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the BURGESS A #1, NE NW SE, Section 21-31-8, Harper County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY [Signature]
 Secretary - Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of February, 1955.

PLUGGING
 FILE SEC. 21 T 31 R 8W
 BOOK PAGE 98 LINE 1

9-11-56

[Signature]
 Notary Public

My commission expires September 24, 1956.