15-077-00055-00-01


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Harper County. Sec. 21 Twp. 31S Rge. 8W (E) (W)
Location as "NE/CNW¼SW¼" or footage from lines ~~NW~~ NW SE NE
Lease Owner Bull Dog Pipe and Supply
Lease Name Harry Burgess Well No. 1
Office Address Box 1153 Tulsa OK.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 7-7 1966
Application for plugging approved 19
Plugging commenced 7-10 1966
Plugging completed 7-15 - 1:30 AM 1966
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Name of Conservation Agent who supervised plugging of this well Archie Elwin
Producing formation Depth to top Bottom Total Depth of Well 4455 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	174	NO
				~~5½~~	~~4455~~	
				5½	4434	3166

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Chat From 4455 To 4375 Dump in.
~~Then~~ 5 Sacks Cement From 4375 To - 4340
Ripped off 5½" Pipe at 3400 - 3300 3250 3200 - 3166.
Pipe came Loose at 3166 and Recovered 3166 - feet of 5½ pipe
Plugged well. Build bridge Top of Fluid 210
with Mud and Rock. Then Mud From 210 To 185
10 Foot of Rock From 185 To 175.
25 Sacks of Cement From 175 To 105
Mud From 105 To 40.
Rock From 40 To 30
10 Sacks of Cement From 30 To Top

Well Plugged -

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1966
8-10-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor CLARKE CORP.
Address Box 187 Medicine Lodge Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Bob Greenberg, dba. Bulldog Pipe & Supply Company (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bob Greenberg
309 Mayo Building
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 66

Lois Britton
Notary Public.

My commission expires 10-24-69

LOG BUREAU -- KANSAS GEOLOGICAL
300 East Murdock, Wichita, Kansas

15-077-00015-0001

Company. MUSGROVE PETROLEUM CORP.
Farm-Burgess "A". No. 1
H Burgess #1

SEC. 21 T. 31 R. 8W
NE NW SE

Total Depth. 4435
Comm. 2-5-55 Comp. 2-20-55
Shot or Treated.
Contractor. Musgrove Petr. Corp.
Issued. 4-23-55

County Harper
KANSAS

CASING:
8 5/8" 174' cem. w/165 sx
5 1/2" 4435'

Elevation. 1576 RB

Production. 141 bbls. oil

Figures indicate Bottom of formations

surface soil	25
redbed, shells & shale	174
shale & shells	600
sandy shale	812
sdy shale & shells	1315
shale & shells	1400
shale & lime	1480
shale & shells	1680
shale & lime	3290
sand & shale	3338
lime & shale	3457
lime & sand	3475
shale & lime	3535
shale & sand	3565
lime & shale	3766
sdy shale & lime	3855
shale & lime	4122
shale & lime strks	4178
shale & hard lime strks	4222
lime & shale	4256
hard lime & shale	4310
shale & lime	4381
Miss. lime	4435
Total depth	

Scout Tops:

Heebner	3367
Toronto	3385
Douglas shale	3430
Douglas sand	3444
Lansing	3604
Stalnaker	3613
Kansas City	3880
Mississippi	4379

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1967
3-9-67
CONSERVATION DIVISION
Wichita, Kansas