

15-077-00957-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 21 Twp. 31 Rge. 8W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Bulldog Pipe & Supply

Lease Name Harry Burgess Well No. 2

Office Address P. O. Box 1153 Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil-depleted

Date well completed September 25, 19 63

Application for plugging filed July 19 66

Application for plugging approved July 19 66

Plugging commenced July 9, 19 66

Plugging completed July 9, 19 66

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4528 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	181'	None
				5 1/2"	4527'	3778'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

181' of 8 5/8' surface pipe, cemented with 150 sacks.  
4527' of 5 1/2' long string, cemented with 150 sacks.  
Top perforation 4399'. Bottom of the hole was sanded  
to 4375', and cemented with 5 sacks, through dump bailer.  
3778' of 5 1/2" long string was recovered from the hole.  
Hole was filled with mud to 200', rock bridge from 200'  
to 190', and cemented with 25 sacks, bringing the top  
of the cement to 120' in the surfacepipe. Hole was filled  
with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks to the base of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation, Inc.

Address Medicine Lodge, Kansas

STATE OF KANSAS COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bob Greenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of January, 19 68

My commission expires 11-5-71

Notary Public.

15-077-00957-0000



drilling company • tulsa

517 RITZ BUILDING TELEPHONE LU 2-1181

Surface Csg.

set 8 5/8" @ 181' w/150 SKs

HE

RAN 5 1/2" net @ 4527'

w/75 Reg. 25 Latex

9-25-63

HARRY BURGESS #2  
NW NE 21-31S-8W  
HARPER Co. KANSAS  
NATIONAL Assoc. Pet. Co.  
Thoroughbred Drilg. Co.  
MIRT 9-12-63  
Compl. 9-25-63

0'-850'- shale: sand

850'-1464'- shale

1464'-1940'- shale: Lime

1940'-2434'- Lime; shale

2434'-2570'- shale: sand

2570'-2715'- Lime - sand - shale

2715'-2875'- Lime - shale

2875'-2991'- shale - sand

2991'-3276'- Lime: shale

3276'-3396'- shale

3396'-3524'- Lime: sandy shale

3524'-3924'- Lime: shale

3924'-4474'- Lime

4474'-4528'- Lime: chat

4528- TD

RECEIVED  
2-28-67

David W. Green