

LEASE NAME Dombaugh

WELL NUMBER 1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 21 TWP. 31 RGE. 8 (E) or (W)

COUNTY Harper

Date Well Completed 1/27/81

Plugging Commenced 7/28/93

Plugging Completed 7/29/93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bison Energy Corporation

ADDRESS 9320 E. Central Wichita, Ks. 67206

PHONE# (316) 636-1801 OPERATORS LICENSE NO. 6581

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 15, 1993 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4391 Bottom 4461 T.D. 4461

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	SEE ATTACHED					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

see attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address 127 E. B St. Attica Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bison Energy Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven C. Anderson, Bison Energy Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 9320 E. Central

Wichita, Ks. 67206

SCRIBED AND SWORN TO before me this 23rd day of August, 19 93

Sondra J. Boyd  
 Notary Public

Commission Expires: May 13, 1995 Sondra J. Boyd

RECEIVED  
 STATE CORPORATION COMMISSION  
 8-24-93  
 AUG 24 1993  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

**SONDRA J. BOYD**  
 Notary Public - State of Kansas  
 Appt. Expires 5-13-95

15-077-20651-0000

7-29-93 Tagged fill up at 4340' (approx 80' of fill), dump 4 sx cement on top of sand. Loaded hole with 18 BBLs of fresh water, pulled stretch on pipe and had 3374' of free pipe. Shot pipe at 3389'. Worked pipe free and pulled 16 jts. casing in 1 1/2 hrs, because tongs were not working correct. Well tried to flow, pumped 55 BBLs down casing to get gas and oil out of casing. Pulled total of 53 jts. casing at 1349', pumped 30 sx cement, 19 BBLs water, pulled 12 more jts. for total of 65 jt at 873' from surface. Pumped 30 sx cement, 13 BBLs water. Pulled 16 more jts total of 81 jts. pipe at 357, circulated cement to surface, pulled 11 more jts. for total of 92 jts. topped off surface pipe with cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 24 1993  
8-24-93  
CONSERVATION DIVISION  
Wichita, Kansas