

15-877-00048-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 21 Twp. 31 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Musgrove Petroleum Corporation
Lease Name BURGESS Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed January 6, 19 55
Application for plugging filed March 7, 19 57
Application for plugging approved March 7, 19 57
Plugging commenced March 28, 19 57
Plugging completed April 2, 19 57
Reason for abandonment of well or producing formation Non-commercial



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production March 15, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Mississippi Depth to top 4382' Bottom 4387' Total Depth of Well 4419 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				5-1/2"	4419'	3378'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Built rock bridge from 4412' to 4370'.
Dumped 5 sx cement at 4370'.
Filled hole with mud to 200'.
Set rock bridge at 200' and dumped 20 sx cement on same.
Filled hole with mud to 35'.
Set rock beidge at 35'.
Dumped 10 sx cement plug from 35' to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wiggins & Lamb Pipe Pulling Company
Address P. O. Box 191, McPherson, Kansas.

STATE OF Kansas COUNTY OF Sedgwick ss.
Emil E. Bowers (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 57

Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

My commission expires June 16, 1959

PLUGGING
FILE SEC 21 T 31 R 8W
BOOK PAGE 145 LINE 45

APR 16 1957
4-16-57
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	BURGESS #1
LOCATION:	NW NW SW, Section 21-31-8 Harper County, Kansas.
COMMENCED:	December 23, 1954
COMPLETED:	January 6, 1955

0	200	Surface soil & shale
200	700	Red & blue shale
700	780	Shale & shells
780	1090	Gummy shale
1090	1200	Anhydrite & shale
1200	1500	Anhydrite & lime
1500	2595	Lime & shale
2595	2770	Lime
2770	3495	Shale & lime
3495	3570	Lime, sand & shale
3570	4369	Lime & shale
4369	4377	Chert & lime
4377	4393	Chert, lime & shale
4393	4419	Chert
	4419	Rotary Total Depth

Set 8-5/8" surface casing at 200' with 100 sacks cement.

Set 5-1/2" casing at 4419' with 125 sacks cement.

STATE OF KANSAS)
)) OS
COUNTY OF SEDGWICK)

I, Gordon L. Koelling, do hereby certify that the above and foregoing is a true and correct copy of the log of the BURGESS #1, NW NW SW, Section 21-31-8, Harper County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of January 1955.

Alma E. Reed
Notary Public

My commission expires July 16, 1955.

REC
STATE CORP
COMMISSION
MAR 1955
3-8-57
CONSERVATION DIVISION

PLUGGING
FILE SEC 21 T 31 R 8W
BOOK PAGE 145 LINE 45