

15-077-18082-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Harper County, Sec. 21 Twp. 31S Rge. 8 ~~28X~~ (W)

Location as "NE/CNW/SE/SW" or footage from lines NW NE SW

Lease Owner Stanolind Oil and Gas Company

Lease Name J. G. Burgess "A" Well No. 1

Office Address Box 1654, Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 6-1- 19 55

Application for plugging filed 7-3- 19 56

Application for plugging approved 7-5- 19 56

Plugging commenced 7-19- 19 56

Plugging completed 7-24- 19 56

Reason for abandonment of well or producing formation Economically Depleted

If a producing well is abandoned, date of last production 3-22- 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Mississippian Depth to top 4379 Bottom 4438 Total Depth of Well 4464 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian	Water	4379		8-5/8	203	None
				5-1/2	4481	3354

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Dumped Sand 4438-4375
- 5 Sx Cement 4375-4345
- Hvy Mud 4345-205
- Crushed Rock 205-190
- 20 Sx Cement 190-130
- Hvy Mud 130-35
- Crushed Rock 35-30
- 10 Sx Cement 30 To Base of Celler

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, SS.  
I, G. A. Reynolds (employee of owner) or ~~(owner or operator)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 7, Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July, 19 56

My commission expires November 12, 1958

[Signature]  
Notary Public.

PLUGGING  
FILE SEC 21 T 31 R 8W  
BOOK PAGE 76 LINE 36

JUL 26 1956  
7-26-56  
CONSERVATION DIVISION  
WICHITA, KANSAS

4481  
3354  
1127



FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand	0	90			
Red Bed	90	211			
Shale, Shells	211	1225			
Shale	1225	1230			
Shells & Anhydrite	1230	1420			
Shale, Shells	1420	1530			
Shale	1530	1570			
lime, Shale	1570	2525			
Shale	2525	3030			
Shale, lime	3030	3424			
lime	3424	3607			
London Top	3607				
lime, Shale	3607	3695			
lime	3695	3825			
lime, Shale	3825	3974			
lime	3974	4213			
lime, Shale	4213	4379			
Missouri Top	4379				
Chart. Oil, Gas & Salt Water	4379	4464			
From Schlumberger Electric Log to T.D.					
Total Depth					
By Schlumberger		4462			
By Rotary Drill		4464			